Project news

PMC decommission gas turbine at Kirriemuir compressor station

A team from PMC Ambergate, consisting of Nick Brown, Richard Latymer and Alan Dales worked for TSG at Kirriemuir compressor station.

Nick Brown explains: "This was a pretty straight forward job for us. We had about 4 days to decommission the compressor cab. To decommission it, we had to take out the bends on the induction and discharge side. After we have lifted these out we then have to cap it off. We put magnetic carriers on the flange and then re-torque the bolts, it is then blanked off and isolated.







